

--SAMPLE PLAN--SAMPLE PLAN--SAMPLE PLAN--

eWaste Disposal, Inc

Sample Rule 1166 Various Locations Mitigation Plan

| Company ID: | XXXXXX | Plan I | ssue Date: | Date |
|------------------|---|--------|---------------|------|
| Mitigation Plan: | XXXXXX | | | |
| Applicant: | Name Address City CA Zip Code | | | |
| Attention: | Contact Name | | | |
| Phone: | (XXX) XXX-XXXX | Fax: | (XXX) XXX-XXX | x |

VARIOUS LOCATIONS Rule 1166 Contaminated Soil Mitigation Plan

Reference is made to your application (A/N XXXXX)-for the excavation and handling of VOC-contaminated soil at various locations within the eWaste Disposal, Inc..

In accordance with Rule 1166 (c), this approved plan is required prior to commencing excavation of any underground storage tank or transfer piping which has previously been used to store or transfer volatile organic compounds (VOC) or during the excavation, handling, or storage of VOC-contaminated soils.

The rights and privileges granted through the issuance of this plan are restricted exclusively to the plan holder to whom it was issued, and are non-transferable, even with the written or expressed consent of the plan holder listed above.

A VARIOUS LOCATIONS PLAN can be used at a site to excavate and remove a maximum of 2000 cubic yards of VOC contaminated soil at the site. Any treatment or additional excavation of VOC contaminated soil at the site will require the issuance of a SITE SPECIFIC plan by the AQMD. Multiple use of VARIOUS LOCATIONS PLANS to excavate over 2000 cubic yards of contaminated soil for the same site is prohibited per Rule 1166.

This excavation and mitigation plan has been approved under the provisions of Rule 1166 of the Rules and Regulations of the AQMD and is subject to the following conditions.



THIS PLAN WILL EXPIRE ONE YEAR FROM THE ISSUE DATE AND THERE IS NO AUTOMATIC RENEWAL PROCESS.

TO MAINTAIN A CURRENT PLAN AFTER THE EXPIRATION DATE, FILE AN APPLICATION FOR A NEW PLAN AT LEAST ONE MONTH PRIOR TO ITS EXPIRATION. CALL (909) 396-2682 OR E-MAIL rvishwanath@aqmd.gov FOR AN APPLICATION PACKAGE AND CURRENT FEE INFORMATION.

PLAN CONDITIONS

SECTION I – GENERAL REQUIREMENTS

- 1. A SIGNED COPY OF THIS PLAN SHALL BE PRESENT AT EACH EXCAVATION SITE AT ALL TIMES AND SHALL BE MADE AVAILABLE TO AQMD PERSONNEL UPON REQUEST.
- 2. THIS PLAN IS NOT VALID FOR THE EXCAVATION OF VOC CONTAMINATED SOILS AT LANDFILLS OR SITES USED FOR DISPOSAL OF REFUSE OR OTHER TYPES OF WASTE.
- 3. THIS PLAN DOES NOT ALLOW THE TREATMENT OF VOC-CONTAMINATED SOIL BY THERMAL, CHEMICAL, OR MECHANICAL PROCESSES. ANY OF THE ABOVE TREATMENT PROCESSES REQUIRES A PERMIT TO OPERATE FROM THE AQMD AND A SITE-SPECIFIC RULE 1166 PLAN.
- 4. THIS PLAN DOES NOT ALLOW BACK-FILLING OF TREATED VOC CONTAMINATED SOIL. BACK- FILLING OF TREATED VOC CONTAMINATED SOIL MAY BE ALLOWED UNDER A SITE SPECIFIC RULE 1166 PLAN.
- 5. THE TOTAL QUANTITY OF VOC CONTAMINATED SOIL EXCAVATED AND HANDLED AT EACH SITE SHALL NOT EXCEED 2000 CUBIC YARDS. THIS TOTAL INCLUDES ANY VOC CONTAMINATED SOILS EXCAVATED FROM THIS LOCATION UNDER A VARIOUS LOCATION PLAN WITHIN THE LAST TWELVE (12) CALENDAR MONTHS. EXCAVATIONS INVOLVING QUANTITIES IN EXCESS OF 2000 CUBIC YARDS OF VOC CONTAMINATED SOIL REQUIRES THE APPLICATION SUBMITTAL FOR A SITE SPECIFIC RULE 1166 EXCAVATION PLAN.
- 6. THE AQMD SHALL BE IMMEDIATELY NOTIFIED OF ANY COMPLAINTS RECEIVED AS A RESULT OF ACTIVITIES CONDUCTED UNDER THIS PLAN. SUCH NOTIFICATION SHALL INCLUDE THE NATURE OF THE COMPLAINT, NUMBER OF COMPLAINANTS AND THE ACTION TAKEN BY THE PLAN HOLDER TO MITIGATE THE SOURCE OF THE COMPLAINT.
- 7. DURING EACH STEP OF THE PROCESS UP TO AND INCLUDING THE REMOVAL AND DISPOSAL PROCESS, ALL PRECAUTIONS AND MEASURES SHALL BE TAKEN TO MINIMIZE THE RELEASE OF VOC, ODOR AND DUST. THIS INCLUDES BUT IS NOT LIMITED TO: THE USE OF ADDITIONAL PLASTIC SHEETING ON STOCKPILES, USE OF SUPPRESSANTS ON EXPOSED SOIL SURFACES & WORK AREAS AND MAINTAINING PAVED PUBLIC STREETS FREE OF SOIL DEPOSITS.
- 8. FOR THE PURPOSES OF RULE 1166 AND THIS PLAN, SOIL MEASURED PURSUANT TO RULE 1166 AS VOC CONTAMINATED SOIL, IS CONSIDERED AS VOC CONTAMINATED SOIL FROM THE TIME OF MEASUREMENT ONWARD, UNTIL THE SOIL IS TREATED PURSUANT TO AN APPROVED AQMD TREATMENT PROCESS.



SECTION II – PRIOR TO EXCAVATION

9. AT LEAST 24 HOURS PRIOR TO COMMENCING EXCAVATION OR GRADING OF SOIL AT THE SITE, THE EXECUTIVE OFFICER OR DESIGNEE SHALL BE NOTIFIED OF THE EXCAVATION BY FAX USING A FORM APPROVED BY THE EXECUTIVE OFFICER WHICH IS FULLY COMPLETED AND INCLUDING, THE NAME OF THE COMPANY PERFORMING THE EXCAVATION, AND THE APPLICATION NUMBER LISTED ON THIS MITIGATION PLAN. THE NOTIFICATION SHALL BE MADE BY FAXING THE NOTIFICATION FORM AT (909) 396-3342, DURING NORMAL BUSINESS HOURS. FAX NOTIFICATIONS WILL RECEIVE A REFERENCE NUMBER BY RETURN FAX OR CAN BE OBTAINED FROM THE AQMD BY PHONE. THE REFERENCE NUMBER SHALL BE RETAINED AS PROOF OF COMPLIANCE WITH THIS REQUIREMENT.

REFERENCE NO:______ NOTIFICATION DATE:____

10. COMPLETE VERIFICATION INFORMATION IN CONDITION NO. 30 AND OBTAIN REQUIRED SIGNATURES, PRIOR TO COMMENCING EXCAVATION.

SECTION III – MONITORING

- 11. DURING THE EXCAVATION PROCESS, AN ORGANIC VAPOR ANALYZER (OVA) SHALL BE ON SITE AT ALL TIMES. THE OVA SHALL BE MAINTAINED IN GOOD WORKING ORDER AT ALL TIMES. AND SHALL BE CALIBRATED BY THE MANUFACTURER AT LEAST ONCE EVERY THREE MONTHS. THE CALIBRATION OF THE OVA SHALL BE VERIFIED USING CERTIFIED CALIBRATION GAS AT THE BEGINNING OF EACH WORKING DAY WITH THE PROCEDURES SPECIFIED BY THE MANUFACTURER. IF A CALIBRATION GAS OTHER THAN HEXANE IS USED, EACH MEASURED READING SHALL BE CORRELATED TO AND EXPRESSED AS HEXANE, USING EQUIVALENCY FACTORS PROVIDED BY THE MANUFACTURER.
- 12. ALL MONITORING SHALL BE CONDUCTED AT A DISTANCE NO MORE THAN 3 INCHES ABOVE THE SOIL SURFACE USING AN OVA DESCRIBED IN CONDITION NO. 11 ABOVE. MONITORING SHALL BE CONDUCTED AT A MINIMUM FREQUENCY OF ONE READING FOR EVERY TWO CUBIC YARDS OF SOIL EXCAVATED, NOT TO EXCEED FIFTEEN MINUTES BETWEEN READINGS. ALL READINGS SHALL BE TAKEN NO LATER THAN THREE (3) MINUTES AFTER EACH LOAD OF SOIL IS EXCAVATED.
- 13. ALL MONITORING SHALL BE CONDUCTED BY TRAINED PERSONNEL WHO ARE PROFICIENT IN THE USE OF THE HYDROCARBON MONITOR SELECTED FOR USE AT THIS SITE.
- 14. WRITTEN RECORDS OF OVA MONITORING AND CALIBRATIONS REQUIRED ABOVE SHALL BE KEPT IN A FORMAT APPROVED BY THE AQMD. THE APPROVED FORMAT IS INCLUDED ON PAGE 7 OF THIS PLAN. THE CERTIFICATION ON ALL RECORDS SHALL BE SIGNED AND DATED ON THE DAY THE MEASUREMENTS ARE OBSERVED.
- 15. UPON DETECTION OF VOC CONTAMINATED SOIL (READINGS 50 PPM OR GREATER), THE EXECUTIVE OFFICER OR DESIGNEE SHALL BE NOTIFIED WITHIN 24 HOURS OF THE FIRST DETECTION OF VOC CONTAMINATION. THE NOTIFICATION SHALL BE MADE BY FAXING THE NOTIFICATION FORM TO (909) 396-3342. A REFERENCE NUMBER WILL BE FAXED BACK OR WILL BE ISSUED WHEN THE FAX NOTIFICATION IS RECEIVED. ALL FAX NOTIFICATIONS SHALL BE FOLLOWED BY MAILING THE NOTIFICATION FORM TO THE DISTRICT POSTMARKED WITHIN 48 HOURS. THE REFERENCE NUMBER WILL BE RETAINED AS PROOF OF COMPLIANCE WITH THIS REQUIREMENT.

REFERENCE NO:______ NOTIFICATION DATE:_____



SECTION IV - HANDLING AND STORAGE

- 16. ALL VOC-CONTAMINATED SOIL BELOW 1000 PPM SHALL BE STOCKPILED, COVERED WITH PLASTIC SHEETING AND STORED SEPARATELY FROM NON-VOC-CONTAMINATED SOIL, OR IMMEDIATELY TRANSPORTED TO A TREATMENT FACILITY.
- 17. A STOCKPILE SHALL NOT CONTAIN MORE THAN 400 CUBIC YARDS OF SOIL.
- 18. IF THE OVA MEASUREMENT IS GREATER THAN 50 PPMV BUT LESS THAN 1000 PPMV
 - A. THE AFFECTED WORK AREA AND LOAD OF SOIL SHALL BE SPRAYED WITH WATER AND/OR APPROVED VAPOR SUPPRESSANT.
 - B. CONTAMINATED SOIL IN STOCKPILES SHALL BE COVERED WITH PLASTIC SHEETING WHICH OVERLAP A MINIMUM OF TWENTY-FOUR INCHES AND ARE SECURED SO THAT NO PORTION OF THE CONTAMINATED SOIL IS EXPOSED TO THE ATMOSPHERE. IN THE COURSE OF HANDLING THE STOCKPILE, ONLY THE WORKING FACE OF THE STOCKPILE MAY BE UNCOVERED.
- 19. IF THE OVA MEASUREMENT EQUALS OR IS GREATER THAN 1000 PPM, STOP EXCAVATION TO NOTIFY THE DISTRICT IMMEDIATELY OR WITHIN ONE HOUR OF DETECTION AND,
 - A. THE AFFECTED SOIL AND WORKING AREA SHALL BE IMMEDIATELY SPRAYED WITH WATER OR AN APPROVED VAPOR SUPPRESSANT, AND EITHER:
 - B. THE CONTAMINATED SOIL EXCAVATED SHALL BE IMMEDIATELY PLACED IN AQMD APPROVED SEALED CONTAINERS, OR,
 - C. DIRECTLY LOADED IN TRUCKS, SPRAYED WITH ADDITIONAL WATER OR APPROVED VAPOR SUPRESSANT, COVERED, AND TRANSPORTED IMMEDIATELY OFF SITE AS PER CONDITION #25 OF THIS PLAN, OR,
 - D. OTHER ALTERNATIVE STORAGE METHODS WITH PRIOR WRITTEN APPROVAL FROM THE AQMD.
- 20. DURING EXCAVATION, THE ONLY EXPOSED VOC CONTAMINATED SOIL SHALL BE RESTRICTED TO THE IMMEDIATE WORKING AREA OF THE SITE OR STOCKPILE. ALL OTHER PORTIONS OF THE STOCKPILE SHALL BE COVERED WITH PLASTIC SHEETING, WITH SEAMS, WHICH OVERLAP A MINIMUM OF TWENTY-FOUR INCHES AND ARE SECURED WITH DUCT TAPE. ANY EXPOSED VOC-CONTAMINATED SOIL SURFACES (WORK FACE) SHALL BE KEPT MOIST WITH WATER OR OTHER APPROVED SUPPRESSANTS AT ALL TIMES, AND SHALL BE RE-COVERED DURING PERIODS OF INACTIVITY LONGER THAN ONE (1) HOUR. AT THE END OF EACH WORKING DAY, ALL STOCKPILES SHALL BE COMPLETELY COVERED AND SECURELY ANCHORED TO PREVENT ANY EXPOSURE OF SOIL TO THE ATMOSPHERE.
- 21. ONCE COVERED WITH PLASTIC SHEETING, STOCKPILES SHALL REMAIN UNDISTURBED UNTIL REMOVED FROM SITE.
- 22. DAILY INSPECTIONS SHALL BE CONDUCTED OF ALL COVERED VOC-CONTAMINATED STOCKPILES TO ENSURE THE INTEGRITY OF THE PLASTIC COVER. SUCH INSPECTIONS SHALL INCLUDE A VISUAL INSPECTION OF ALL SEAMS AND PLASTIC COVER SURFACES. ANY HOLES, TEARS OR ANY OTHER POTENTIAL SOURCES OF FUGITIVE VOC EMISSIONS SHALL BE REPAIRED IMMEDIATELY. DAILY RECORDS SHALL BE MAINTAINED TO ENSURE COMPLIANCE WITH THIS



CONDITION.

23. VOC CONTAMINATED SOIL SHALL NOT BE SPREAD ON-SITE OR OFF-SITE. THIS INCLUDES ANY UNNECESSARY MOVEMENT OR AGITATION OF SOIL THAT MAY CAUSE THE UNCONTROLLED EVAPORATION OF VOC'S INTO THE ATMOSPHERE, INCLUDING THE RESHAPING OR RELOCATION OF STOCKPILES.

SECTION V - SOIL REMOVAL AND DISPOSAL

- 24. ALL EXCAVATED VOC-CONTAMINATED SOIL SHALL BE REMOVED FROM THE SITE WITHIN **THIRTY (30) DAYS** OF ITS EXCAVATION.
- 25. ALL VOC-CONTAMINATED SOIL REMOVED FROM THE SITE SHALL BE TRANSPORTED TO AN APPROVED TREATMENT/DISPOSAL FACILITY. IF THE RECEIVING FACILITY IS LOCATED WITHIN THE AQMD'S JURISDICTION, IT SHALL BE THE RESPONSIBILITY OF THE PLAN HOLDER TO ENSURE THAT THE RECEIVING FACILITY POSSESSES THE REQUIRED AQMD PERMITS AND PLANS.

SECTION VI - RECORDS AND REPORTING

- 26. A WRITTEN REPORT SHALL BE PROVIDED TO THE AQMD WITHIN 30 DAYS OF INITIAL DETECTION OF CONTAMINATED SOIL, WHICH INCLUDES THE FOLLOWING INFORMATION.
 - A. THE STATUS OF THE EXCAVATION PIT, AND ANY VOC CONTAMINATED SOIL REMAINING ON SITE.
 - B. A BRIEF SUMMARY INDICATING IF ADDITIONAL CLEAN UP EFFORTS ARE NECESSARY, THE ADDITIONAL QUANTITY OF VOC CONTAMINATED SOILS TO BE EXCAVATED AND THE PROJECTED SCHEDULE OF THE EXCAVATION.
- 27. RECORDS OF DISPOSAL SHALL BE MAINTAINED FOR ALL VOC-CONTAMINATED SOIL REMOVED FROM THIS SITE. SUCH RECORDS SHALL BE CLEARLY LABELED "SCAQMD RULE 1166-VOC CONTAMINATED SOIL" AND SHALL INCLUDE THE IDENTIFICATION AND THE LOCATION OF, 1) THE GENERATOR, 2) TRANSPORTER AND 3) RECEIVING FACILITY. IN ADDITION, SUCH RECORDS SHALL BE SIGNED AND DATED BY EACH OF THE ABOVE PARTIES INDICATING RECEIPT OR RELINQUISHMENT OF THE VOC-CONTAMINATED SOIL AT THE TIME CUSTODY IS TRANSFERRED.
- 28. RECORDS OF DISPOSAL OF VOC-CONTAMINATED SOIL SHALL BE MAINTAINED ON SITE DURING THE EXCAVATION AND LATER MAINTAINED FOR A PERIOD OF TWO (2) YEARS. THE RECORDS SHALL BE MADE AVAILABLE TO AQMD PERSONNEL UPON REQUEST.
- 29. WITHIN THIRTY (30) DAYS AFTER THE EXCAVATION AT THE SITE IS COMPLETED, THE WRITTEN RECORDS UNDER CONDITIONS NO. 14, 22, AND 27 SHALL BE SUBMITTED TO THE AQMD AT THE FOLLOWING ADDRESS.

eWaste Disposal, Inc.

(RULE 1166 COMPLIANCE) OC Location: 1048 Irvine Ave, Suite 1069, Newport Beach CA 92660 LA Location: 13037 Lakeland Ave Suite A, Santa Fe Springs CA 90670



30. THIS PLAN IS NOT VALID UNTILL ALL PARTIES HAVE REVIEWED AND SIGNED THE VERIFICATION STATEMENT BELOW.

SECTION VII - VERIFICATION AND SIGNATURE

| Site Name | | Type of Business | |
|------------------------------------|------|------------------|-----|
| | | | |
| Address | City | | Zip |
| | | | |
| Responsible Party (Owner/Operator) | | Pho | ne |
| | | | |
| Address | City | | Zip |
| | | | |

I CERTIFY THAT I HAVE REVIEWED AND UNDERSTAND THE CONDITIONS CONTAINED WITHIN THIS PLAN. IN SIGNING BELOW, I ACKNOWLEDGE THAT UNDER THE PROVISIONS OF RULE 1166, I CAN BE HELD RESPONSIBILE FOR THE REQUIREMENTS SET FORTH IN THIS PLAN.

| Responsible Party | Responsible Party Signature | Date Signed |
|--------------------------|------------------------------------|-------------|
| | | |
| General Contractor | General Contractor Signature | Date Signed |
| | | |
| Excavation Contractor | Excavation Contractor Signature | Date Signed |
| | | |
| Environmental Consultant | Environmental Consultant Signature | Date Signed |
| | | |

DEFINITIONS

| Excavation | Is the process of digging out and removing materials including any material necessary to that process such as the digging out and removal of asphalt or concrete necessary to expose, dig out and remove known VOC contaminated soil. |
|------------------------------|---|
| Organic Vapor Analyzer (OVA) | For the purposes of this plan, an OVA is an hydrocarbon monitor utilizing flame ionization, photo ionization or other analytical methods complying with 40 CFR PART 60 APPENDIX A, EPA METHOD 21 SECTION 3, "DETERMINATION OF VOLATILE ORGANIC COMPOUND LEAKS, MONITORING INSTRUMENT SPECIFICATIONS. The monitor shall be capable of being calibrated using hexane at a range of 0 parts per million by volume (PPMV) to 50 PPMV, and at a detection range of at least 30 PPMV to 1100 PPMV |
| Responsible Party | For the purposes of this plan, Responsible Party is the party financially responsible for initiating the excavation. This may include the property owner or the tank operator. This excludes contractors working for the property owner or operator, |



and any other party that lacks the direct authority to immediately treat all VOC contaminated soils generated at the excavation site.

| VOC Contaminated Soil | Is soil that registers a concentration of 50 PPM or greater of volatile organic compounds as measured before suppression materials have been applied and at a |
|-----------------------|---|
| | distance of no more than three inches from the surface of the excavated soil with an organic vapor analyzer calibrated with hexane. |

Volatile Organic Compound (VOC) Is any volatile compound of carbon, excluding methane, carbon monoxide, carbon dioxide, carbonic acid, metallic carbides or carbonates, ammonium carbonate, and exempt compounds. Exempt compounds areas defined in Rule 102 – Definitions of Terms.

Once issued, this plan is subject to further review by the AQMD and may be revoked if excavation activities are found in violation of plan conditions or AQMD's Rules and Regulations. Failure to comply with one or more of the conditions contained within this plan constitutes a violation of Rules 221 and 1166.

Other governmental agencies may require approval before any excavation begins. It shall be the responsibility of the applicant to obtain that approval. eWaste Disposal, Inc. shall not be responsible or liable for any losses because of measures required or taken pursuant to the requirements of this approved 1166 Contaminated Soil Mitigation Plan.

Questions regarding this plan should be directed to Thomas M Abercrombie at 949-466-8857.

Best regards,

Thomas M Abercrombie A.Q.A.C. Supervisor

Rule 1166 Soil Monitoring Records

| Company Name | Facility/Site Information | | |
|------------------|---------------------------|------|--|
| | | | |
| | | | |
| Plan #: | Name: | | |
| | | | |
| ID #: | Address: | | |
| Reference No(s). | City: | Zip: | |
| | | | |



| Monitor Information | Calibration Data | Monitoring Personnel | Excavation Summary (Upon completion of each page) | |
|---------------------|------------------|----------------------|--|--|
| Brand: | Gas: | Name: | Total Cubic Yds | |
| | | | (This page) | |
| Model: | Date | Company: | Total Cubic Yds | |
| | | | (To date) | |
| Туре | Ву | Phone: | Removed from | |
| | | | Site (To date) | |

| Time | VOC Concentration (PPMV) @ Excavated Load | | Comment | Time VOC Concentration (PPMV)@ Excavated Load | | | Comment | | |
|---------|--|--------|----------|--|---------|---------|---------|----------|--|
| Every | Reading | Hexane | Adjusted | | Every | Reading | Hexane | Adjusted | |
| 15 min. | • | Factor | Reading | | 15 min. | - | Factor | Reading | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | - | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |
| | | | | <u> </u> | | | | | |
| | | | | | | | | | |
| | | | | | | | | | |

I certify that the information contained in the above document is true and correct. I further certify that the above listed hydrocarbon monitor was operated in a manner consistent with the manufacturer's specifications and the conditions specified within this plan. In addition, I certify that the above readings represent the actual measurements I observed and recorded during the excavation process.

SIGNATURE:_____

DATE:_____